

Cunard Express Steamers S.S. "LUSITANIA" & S.S. "MAURITANIA",  
building by Messrs John Brown & Co, Clydebank, and Messrs  
Swan, Hunter & Wigham Richardson, Wallsend on Tyne, respectively.

-----  
EQUIPMENT.  
-----

Rule Dimensions; 757 x 87.5 x 62.

Equipment No. about 170,000.  
-----

The following equipment is proposed by the Builders  
at the Owner's request for the above vessels, viz-

1 Bower Anchor (Stockless)			10 Tons.
1 " " "			10 "
1 " " "			8½ "
1 Kedge " (ex Stock)			2 "
Chain Cables	330 fathoms		3¾" (stud link)
Steel Wire Hawsers	2 at 90	"	8"
" " "	1 " 150	"	7"
" " "	2 " 120	"	3¾"
" " "	2 " 120	"	3½"
Manilla Warps	2 " 90	"	10"
" "	10 " 120	"	8"
" "	2 " 120	"	6"

With a view to facilitate the handling of these vessels  
the Owners propose to dispense with a stream anchor and to have  
a kedge anchor weighing 2 tons as shewn above.

It is submitted that the proposed equipment merits the  
favourable consideration of the Committee.

*Mr. G. 4.06*  
*Ans. 12<sup>th</sup>*  
*P.C. Memo to Mr. C.*

*Approved by Chairman*  
*as. 12/4/06*

*J. H. C.*

*11/4/06*



© 2018  
Lloyd's Register  
Foundation