

REPORT of SURVEY for REPAIRS, &C.

Date of writing Report 26/8/95 When handed in at Local Office

Port of London

No. in Reg. Book Survey held at London

Date, First Survey 1st July Last Survey 23rd August 1895

44 Sup 1316 on the Wood? Iron or Steel Comp. S. "FERREIRA", ex butty bark Master Sebastiao dos Santos Pereira, 95.95

TONNAGE: Built at Dumbarton By whom Scott & Linton When 1869

GROSS 963 Owners J. A. Ferreira & Co Port belonging to Lisbon

UNDER DE. 892 Owners' Address Lisbon

NET 921 (if not already recorded in Appendix to Register Book.)

Surveyed Afloat or in Dry Dock? Both Name of Dock Amor's dry dock Destined Voyage Lisbon

WB=Cell D Bor DBa tons; uE&B tons; f tons; Particulars of Classification (which must be inserted precisely as in Register Book & Supplements).

FPT tons; APT tons; MT tons.

N.B.—All alterations in the existing records should be underlined.

If the vessel has Water Ballast Tanks, state whether the manhole covers have been removed, and the insides of the tanks examined. Also state the amount of deterioration (if any) found in the thicknesses of the floors, framing, girders, and of the inner bottom plating, especially in the boiler space.

Last Survey, No. 5338 Port Low

Periodical Surveys, when held, must be reported in detail and serialim in the terms of the Rules. State clearly the cause of Repairs, if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Repairs on account of Damage (the cause of which must be stated) should be separated from Repairs due to other causes; and besides being detailed in the body of the report, should be summarised in the form shown below. Whenever the replacement of Anchors, Chains, or Hawsers is reported, the particulars of weight or size and test of the articles should be clearly stated, and also the weight or size, &c., required by the Rules, together with the vessel's Equipment for, if any. State also the dates and initials of any letters respecting this case.

CHARACTER & for Special Survey, Date of last Survey and of Periodical Surveys.	Year of Survey	Machinery and Boiler Surveys (including date of N.B., if any).
Cont 13 A I	19	
from 12.88, Lon		
+ 4.94		
S.S. Apt 93		
Society's Freeboard (if assigned) as painted on Ship and now verified	4	3 ins.

REPAIRS, OR EXAMINATION AS PER RULE, FOR Condition, Change of Name and Owners

Repairs now done on account of Wear & Tear:— Vessel placed in dry dock, bottom in way of yellow metal sheathing re-caulked; caulking tested and bottom examined: Two defective portions of false keel renewed with elm; Rudder lifted and repaired where necessary: False stem re-fastened: Bottom resheathed with yellow metal on felt: Jibboom, spanker boom, and main upper topsail yard renewed: New iron windlass by Messrs Walker & Thompson of Gateshead fitted: New main steam winch fitted and arranged to work windlass by means of messenger chain

SUMMARY OF DAMAGE REPAIRS:—	Plates.	Frames.	R. Frames.	Floors.	Beams.	Other Items:—
Renewed	✓	✓	✓	✓	✓	✓
Faired or Repaired ...	✓	✓	✓	✓	✓	✓

PRESENT CONDITION OF THE	Timbers of Frame at the openings	Rudder	Hatches
is <i>Good</i>	<i>Good</i>	<i>Good</i>	<i>Good</i>
ways <i>"</i>	ditto at other places <i>"</i>	Windlass & Capstan <i>"</i>	Boats <i>"</i>
ings <i>"</i>	Keelsons <i>"</i>	Pumps <i>not tested</i>	Masts, Yards, &c. <i>"</i>
Dk. Beams & Fastenings <i>"</i>	Clamps, Shells & Stringers <i>"</i>	Sluice Valves <i>not seen</i>	Condition, how ascertained <i>from deck</i>
r Dk. Beams & Fastenings <i>"</i>	Salting (State if examined.) <i>"</i>	Watertight Doors <i>"</i>	(State if wedges removed) <i>no</i>
ing <i>"</i>	Ceiling <i>"</i>	Dbing. Plates under Sounding Pipes <i>"</i>	Sails <i>good</i>
king <i>"</i>	Cement or Asphalt <i>not seen</i>	Engine-Room Skylights <i>Good</i>	Equipment letter ✓
nails or Rivets <i>"</i>	(State which.) <i>"</i>	Coal-Bunker, Open'gs, Lids, &c. <i>"</i>	Anchors, No. of <i>3B-15-2K</i>
sthooks & Stemson <i>"</i>	Tanks (State if now tested.) <i>none</i>	Scuppers <i>"</i>	Cables (State if now ranged) <i>no</i>
uoms, Pointers, & Crutches <i>not seen</i>	Caulking of Bot'm, D'k, & Wat'r'ys <i>good</i>	Cargo & Main H'tch'ys <i>"</i>	" length ✓ size ✓
	Cappon or Y.M. on felt (State if on Felt.) <i>felt</i>		" Rule length ✓ size ✓
	When put on, Month <i>July</i> Year <i>1895</i>		Hawsers & Warps <i>Sufficient</i>
			Standing & Running Riggings <i>good</i>

General Observations, Opinion as to Class, Recommendation, &c.:

State clearly whether any and, if so, what alteration is suggested to be made in the existing classification and notification of the vessel in the Register Book consequent upon this survey, thus, for example:— "to remain as now classed in the Register Book without fresh record of Survey," "to remain as classed and to have record of survey, 9.91," or "to remain as classed and to have record of survey, 9.91, and the notations of ss. No. 1-91 and p1ND91, &c."

This vessel is now in a good and efficient condition and eligible in our opinion to remain as classed and to have record of survey 8.95 Lon and the notation of F & YM 7.95 in the Register Book

Office Fee (if chargeable) per Scale II., Sec. 27	Survey Fee (per Section 28)	Special Damage or Repair Fee (if any) (per Sec. 28.)	Travelling Expenses (if chargeable)	Second Surveyor's Fee (if any)
£	£	£	£	£
		Less 10% 2	19	

Fees applied for, 28/8/95

Received by us, 31/8/95

Wm Morrison

Surveyor to Lloyd's Register of British & Foreign Shipping.

Committee's Minute Character assigned

FRI. 30 AUG 1895

Cont 13 A I

72 YM 7.95

HULL CERTIFICATE WRITTEN. 4/10/95



© 2018

Lloyd's Register Foundation