

Q. T. S. S. "AQUITANIA" - W. T. SUBDIVISION.

Extract from a letter to Dr. Thearle from Mr. Mares - 12.6.12.

"I may also say that in the "AQUITANIA" it has been decided to extend the following bulkheads to "D" deck, viz: at frames 11, 43, 79, (156 at side 163 at centre) 222 & 246.

The question of fitting additional stiffening to the lower portion of the bulkheads is, I understand, under consideration.

It has also been decided to make "G" deck watertight from end to end, and where this deck does not exist in way of engine rooms to make the "F" deck watertight.

The hatchways to Nos. 1, 2 & 3 holds will be trunked from "G" deck to the shelter deck and made watertight".



© 2018

Lloyd's Register
Foundation