

No. 955.

460' 0" x 66' 0" x 36' 0" Mld. to Awning Deck.

Approximate Freeboard Particulars.

Length on Summer load waterline from fore side of stem to aft side of stern post)	≠	460' 0"
Breadth Moulded	66' 0"
Depth Moulded to Awning Deck	36' 0"
Block Coeff. at .85 depth to Awning Deck68
Sheer at A.P.)	...	4' 8"
1/6 L from A.P.)	...	2' 0"
1/3 L " ")	...	5 1/4"
Amids.)	Awning Deck	1 1/8"
1/3 L from F.P.)	...	1' 2 3/8"
1/6 L " ")	...	4' 3 5/8"
F.P.)	...	9' 4 1/8"
Rise in sheer Amidships)	...	1 1/8"
Round of Beam	4"
Erections: Complete Superstructure of Superimposed Bridge and Forecastle.			

≠ Greater than 96% of total length on L.W.L.

