

Lloyd's Register of Shipping.

Ship's Name

"EMPIRE CEDRIC"

Official No. 181506 6 MAY 1948

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in Belfast.

1. New steel companion way fitted on Port and Starboard sides of upper deck forward to new accommodation in upper 'tween deck, strongly constructed with 21" coaming and fitted with a 2" solid wood door operated from both sides (opening 6'0" x 2'3"). ✓
2. New 16" portlights fitted in sheer strake, 7 Port and 11 Starboard side in way of new accommodation, steelwork stiffened similar to existing portlights with 5" x 3" x .40" B.A. each side of opening. Portlights are fitted with deadlights. ✓
3. 24" steel plating coaming fitted in Bow door Machinery compartment on Port & de. ✓
4. Two-2" scuppers, two-2" basin discharges and two-4" soil discharges from new accommodation on main deck forward discharge below main deck through storm valves. ✓

Copy of this report placed on board the vessel.

H. Darnley.

12th May 1948

Holled

27 MAY 1948

MLD