

44693

Report of Survey for Repairs, &c., of Engines & Boilers.

No. (Received at London Office.)

No. in Reg. Book. *32* Survey held at *London* Date, first Survey *1st Feb* Last Survey *24th Feb 1885*

on the Machinery of the *Screw Steamer "Aberdeen"* (Number of Visits)

Tonnage, Gross *3616* Built at *Glasgow* When built *1881-12*

Ditto, Net *2371* Owners *J. Thompson & Co* Port belonging to *Aberdeen*

Diameter of Cylinder *30, 45 & 70* Engines made by *R. Napier & Sons* When made *1881*

Length of Stroke *54"* Boilers made by *Do* When made *1881*

Pressure of Steam *125 lbs* If Surveyed Afloat or in Dry Dock *At East India Docks* Character in Register Book. *100A1*

Registered Horse Power *400* (State name of Dock.)

Last Survey No. *9.84* Port *+ L.M.C. 2.84*

Particulars of Repairs and Examination *Annual*

(State clearly the cause of Repairs if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Repairs on account of Damage should be separated from Repairs due to other causes. State also the dates and initials of any letters respecting this case.)

Examined Engines and Boilers internally and externally, found two of the furnaces had slightly collapsed; recommended them to be heated and set back with powerful hydraulic jacks, which was done; the Boilers cleaned and scaled and placed in good working condition.

The cylinders, valves, pistons and all working parts of the Engines were examined and placed in good working order.

General Observations, Opinion, and Recommendation:— *I am of opinion that this vessel is eligible to remain as classed in the Society's Register Book.*

(State clearly what alteration, if any, is suggested to be made in the existing notification of the vessel's machinery in the Register Book, consequent upon this survey.)

Office or Registration Fee (per Sec. 27)	£	:	:
Survey Fee (per Section 28) <i>26/2/85</i>	£	1	0
Special Damage Fee (per Section 28)	£	:	:
*Certificate (if required)	£	:	:
Travelling Expenses (if chargeable)	£	:	:

received by me, *W.P.*
3.9 1885

William Parker
Engineer Surveyor to Lloyd's Register of British and Foreign Shipping.

Committee's Minute

FRIDAY 27 FEB 1885

Assigned

This Report is also sent to the Hull of the Ship

Insert Character of Ship and Machinery precisely as in the Register Book.