

(L L O Y D S R E G I S T E R). Lloyds Register
VESSELS OF 100 TONS AND UPWARDS.

Form No. 19. These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyds Register of British and Foreign Shipping.

Signal Letters (if any) K.L.F.G.

Official Number. 146,266.	Name of Ship. DOMALA.	No., Date, and Port of Registry. 64/1921. Glasgow.	
No., Date, and Port of previous Registry (if any) -----			
Whether British or Foreign Built. British	Whether a Sailing or Steam Ship; and if a Steam Ship, how propelled. Motor Ship Twin Screw	Where Built. Whiteinch	Name and Address of Builders. Barclay Curle & Co.Ld. Whiteinch.
Number of Decks Two	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post 450	Feet. 450	Tenths. .
Number of Masts Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel 449	449	6.3
Rigged Schooner	Main breadth to outside of plank 58	58	3.
Stern Elliptical	Depth in hold from tonnage deck to ceiling at midships 32	32	9.5
Build Clencher	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards		
Galleries None	Depth from top of beam amidships to top of keel 35	35	5.
Head Straight	Depth from top of deck at side amidships to bottom of keel 35	35	7.4
Framework and description of vessel Passenger & Cargo Vessel	Round of beam 1	1	1.7
Number of Bulkheads Eight	Length of engine room (if any) 56	56	3.
Number of water ballast tanks, and their capacity in tons Nine 1650 tons.			

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel **15247** Tons. Ditto per inch immersion at same depth **51** Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. B. H. P. I. H. P. Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.		
Two	Vertical Four Stroke Reversible Single	British	1921	North British Diesel Engine Works Ltd. Whiteinch	Eight 26½ "	47 "		962. 4000 4666 12½ Knots.
Two	Particulars of Boilers.	Boilers.	Boilers.					
	Description Number Iron or Steel Loaded pressure							

PARTICULARS OF TONNAGE.

GROSS TONNAGE.			No. of Tons.	DEDUCTIONS ALLOWED.			No. of Tons.
Under Tonnage Deck			6848.27	On account of space required for propelling power...			2701.04
Space or spaces between Decks				On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from Goods or Stores of every kind, not being the personal property of the Crew			
Turret or Trunk			61.12	These spaces are the following, viz. :—			
Forecastle (and Houses in)			536.72	Below deck, Forecastle, Bridge, Poop, Round and Side Houses.			491.11
Bridge space			154.34	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows :—			
Poop or Break			22.05	Cubic Metres. Master 15.37)			
Side Houses			788.12	Boatswains Store 29.09)			
Deck Houses			6.90	Wireless House 5.72)			114.24
Chart House			23.23	Chart House 6.90)			
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894,				Water Ballast Spaces 57.16)			
Excess of Hatchways			8440.75	Total			3306.39
Gross Tonnage			3306.39				
Deductions, as per Contra			5134.36				
Registered Tonnage			14530.24				

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is **1145.82** tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is **144.72** tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage :

Passages in Forecastle	L.21.0 -- 9.56 Tons
	L.11.9 -- 3.78 Tons
	L.31.0 -- 9.22 Tons.

Name of Master.	Certificate of { Service No. Competency No.
Names, Residence and Description of the Owners, and } viz., Number of Sixty-fourth Shares held by each ... }	
British India Steam Navigation Company Limited 122, Leadenhall Street, London E.C. --- Sixty-four(64) shares.	
Duncan Carmichael, Kt, same address- Manager.	

Dated **21st November, 1921.**