

COPY.

# Lloyd's Register of Shipping,

71, Fenchurch Street, E.C. 3.

ENCLOSURES.

9th September, 1935.

Dear Sirs,

E.

I duly received your letter of the 2nd instant respecting the Loeffler-Escher-Wyss installation proposed for the ss. "CONTE ROSSO", and with regard thereto I have to inform you that the plans of high pressure and low pressure water separators will be approved for a working pressure of 140 kg/cm<sup>2</sup> and 14 kg/cm<sup>2</sup> respectively, provided the upper circumferential weld of the low pressure separator be not less than 50 mm. distant from the end of curvature of the dished end plate, the welding be carried out to your entire satisfaction, and the separators be otherwise constructed under the usual conditions of survey and testing.

Two copies of the plan forwarded by you are returned herewith, the remaining copy being retained in this Office.

I am, Dear Sirs,

Yours faithfully,

Secretary.

The Surveyors,  
TRIESTE.



© 2018

Lloyd's Register  
Foundation

LR-885-7A7-21