




"CONTE ROSSO"

Loeffler Boiler Installation.

Water Separators.  
-----

IT IS SUBMITTED the plans of High pressure and low pressure water separators merit approval for a working pressure of  $140 \text{ kg/cm}^2$  and  $14 \text{ kg/cm}^2$  respectively, provided the upper circumferential weld of the low pressure separator be not less than 50 mm. distant from the end of curvature of the dished end plate, the welding be carried out to the entire satisfaction of the Surveyors, and the separators be otherwise constructed under the usual conditions of survey and testing.

LW 9/9.

  9.9.35.  




© 2018

Lloyd's Register  
Foundation