

The Scottish Tube Coy. Ltd.

Govan Tube Works,

Helen Street, Govan. 12th. Decr. 1922

Specification of welded wrought iron Tubes for Alex. Stephen & Sons.
Linthouse.

Order Page No. 28 of 8/12/22.

Contract No. 499.

3 Bent Pipes Nos. A/37, A/38, A/40 made from $6\frac{1}{2}$ " o/d x $5/16$ " thick tube
screwed at ends and fitted with flanges to diameters and thicknesses
as specified, screwed on, faced plain, and having tube ends expanded
into flanges.

All Pipes annealed.

Working Pressure	215 lbs per square inch
Test Pressure	645 lbs per square inch

All to Lloyds Requirements.

Test carried out 12¹²/₂₂. R.R.D.



© 2018

Lloyd's Register
Foundation