

The Scottish Tube Co. Ltd.,
Govan Tube Works,
Govan.

20th. Decr. 1922.

S P E C I F I C A T I O N of Lapwelded W. I. Pipe for Messrs. Alex. Stephen
& Sons, Ltd., Engine Dept., Linthouse.

Order No. E.713 of 29/6/22.

Contract No. 499.

Main stem in ER

1 - Bent Pipe made from 7-1/2" od. x 11/32" thick Lap. Tube. No. A.35.

Screwed at ends with vanishing threads and fitted with Wrot. Iron Stamped
Flanges to diameters and thicknesses as specified, screwed on, faced plain,
turned on edge and having tube ends expanded into Flanges.

Above Pipes annealed.

Working Pressure.

215 lbs. per Square inch.

Test Pressure.

645 lbs. per Square inch.

All to Lloyd's Requirements.

H. H. G.



© 2018

Lloyd's Register
Foundation