

The Scottish Tube Co. Ltd.,  
Govan Tube Works,  
Helen Street,  
GOVAN.

15th. January 1923.

S P E C I F I C A T I O N of lapwelded Wrot. Iron Pipes for  
Messrs. Alex. Stephen & Sons, Ltd., Linthouse.

Order No. 1/11/22.

Contract No. 498. *499.*

1 - Bent Pipe made from 7-1/2"<sup>*main stem*</sup>od. x 11/32"thk. Tube, No. A.36.

All screwed at ends with vanishing threads and fitted with Wrot. Iron  
Stamped Flanges to diameters and thicknesses as specified, screwed on,  
faced plain, turned on edge and having tube ends expanded into Flanges.

Working pressure.

215 lbs. per Square inch.

Test Pressure.

645 lbs. per Square inch.

All to Lloyd's Requirements.

*Amh.*



© 2018

Lloyd's Register  
Foundation