

S.M.V. BRITISH PRIDE

LONGITUDINAL FRAMING.

THE SCANTLINGS AND DETAILS OF CONSTRUCTION NOTED HEREON ARE SUBMITTED ON THE UNDERSTANDING THAT THEY ARE THE MINIMUM WHICH WILL BE ACCEPTED FOR CLASS. ERRORS AND OMISSIONS EXCEPTED.

EQUIPMENT		NUMBER	
SECOND LONGITUDINAL	NUMBER	$L = (B + D)$	= 405.2
POOP		$10.5 \times 8.0 \times \frac{\pi}{2}$	= 664
BRIDGE		$42.0 \times 8.0 \times \frac{\pi}{2}$	= 252
FORECASTLE		$82.5 \times 8.0 \times \frac{\pi}{2}$	= 375
POOP HOUSE & CASING		$107.0 \times 8.0 \times \frac{\pi}{2}$	= 428
BOAT DECK	CASING	$12.0 \times 8.0 \times \frac{\pi}{2}$	= 84
"	"	$32.0 \times 4.0 \times \frac{\pi}{2}$	= 84
HOUSES ON BRIDGE DECK		$35.5 \times 8.0 \times \frac{\pi}{2}$	= 112
CHART & WHEEL HOUSE		$33.5 \times 7.5 \times \frac{\pi}{2}$	= 126
		EQUIPMENT NO.	= 4824.7

EQUIPMENT.			
2	BOWER ANCHORS	7 7/8" x 7 7/8" CUTS STOCKLESS	
1	BOWER ANCHOR	62 CUTS STOCKLESS	
1	STORM ANCHOR	9 2 1/2" CUTS EX. STOCK	
300	RATHIONS	2 5/8" STUD LINK CHAIN CABLE 6 1/4" x 4" CUTS	
120	RATHIONS	5 1/2" STEEL WIRE	
130	RATHIONS	5 1/2" STEEL WIRE	
2	HAWKERS	100 RATHIONS EACH 6 HERCULES BRAND MANILLA	
2	WARPS	100 RATHIONS EACH 8 " " " "	BUILDER
1	HAWKERS	80 " 8 1/4" STEEL WIRE	
2	"	90 " 3 1/2" " " "	
2	"	90 " " " "	OWNED
4	"	100 " 7" HERCULES BRAND MANILLA	

LITHGOWS LTD

Nº 849.

M.V. "BRITISH PRIDE"

MIDSHIP SECTION
(AS BUILT)

Gk Rep Nº. 19294.

4 Photostats

RETAIN



© 2019

Lloyd's Register
Foundation

002000-002012-0042