

Lloyd's Register of Shipping.

Ship's Name "BEN VOOAR."

Official No. 136358.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines

in X not known area

HATCHWAY RENEWED except for fore end coaming.
 Size. 38'-6" x 14'-0". Coaming 2'-9" x 38" with stiffeners 7" x 3" x 38" 3 in.
 4 stay brackets (6" channel bar). Hatch beams 7 in number, 4'-10 $\frac{1}{2}$ " apart. Plate 15 x 31 with angles, double, 3" x 3" x 42" top and bottom.
 Wood Hatch covers 2 $\frac{1}{2}$ thick laid fore and aft, bearing surface 3'
 cleats 21"-24" apart. 3 tarpaulins together with eyebolts and lashings.
 The Owner's copy of original freeboard report has been altered
 as above and dated 30/12/46. The approved plan of hatchway
 is enclosed herewith. See also C11(c) N° 71343 dated 23rd Dec². 1946
 and application 30/12/46.

ML-W

Noted
C-1
8-1
8 JAN 1947