



# Lloyd's Register of Shipping.

Maritime Buildings, East Dock Street,

Dundee, 9<sup>th</sup> Feb. 1928

LLOYD'S REGISTER  
RECEIVED  
10 FEB 1928  
LONDON

Reference

S.

Dear Sir.

I have to confirm telegram sent  
to you as under;  
Sent 8-2-28.

" BRITISH FAITH REFERENCE LETTER SEVENTH  
ALL ITEMS FITTED AS APPROVED STOP  
TELEGRAPHING PARTICULARS DOUBLE BOTTOM AT  
9 AM THURSDAY".

Sent 9-2-28.

" BRITISH FAITH OVERALL LENGTH OF DOUBLE  
BOTTOM AFT 85 FEET 1 INCH TOTAL CAPACITY 310.6 TONS  
THIS INCLUDES CIRCULATING WATER SETTLING TANK  
FEED TANK LUBRICATING OIL DRAIN TANK AND OIL  
FUEL TANK BELL.

With reference to the above and to your  
letter of the 7<sup>th</sup> inst., I beg to state that the  
thickness of the side girders in the fore hold is .42  
approved .4, the tank side brackets in the machinery

002024-002031-0008 1/2



# Lloyd's Register of Shipping,

Maritime Buildings, East Dock Street,

Dundee,



enc

space is 48 as approved, the spacing of the second deck beams forward is 27" & 24" as approved, the second deck stringer plate 44 as approved, the number of vertical webs on the midships bulkheads are 2 each side of centre line as approved and the stiffeners on the after peak bulkhead are 9" x 3" x .58 BA to 5" x 3" x .50 OA. as approved.

I enclose an outline sketch of the double bottom aft showing the arrangements of the compartments with their lengths and capacities.

I am, Dear Sir,

Yours faithfully

H. W. Bell.

The Secretary.


London.

P.S. I may say that I was doing duty in Aberdeen on the 8<sup>th</sup> inst. and did not return to Dundee until the evening when I received your letter and sent you a telegram at 10-30 pm.

002024-002037-0008

Aug. 2/2

enclosure attaches at back of report



© 2020

Lloyd's Register Foundation



Referred to the Chief Ship Surveyor.

Jan 8

10 FEB 19'8

13.2.28

Drucke

Maritime Buildings, West Dock Street

Shipping to Foreign Ports



© 2020

Lloyd's Register  
Foundation