

29001  
Feb. 7864

21 SEP 1949

Rpt. C. 11 (Contd.)

Index No. ....

# Lloyd's Register of Shipping.

Ship's Name "DRANSFIELD" Official No. 145595.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

## Hatchways.

The wood fore & afters & beams to Nos. 1 & 2 Hatchways have now been replaced with transverse hatch beams, 3" wood hatch covers renewed & fitted fore & aft.

Particulars of new hatch beams:—

Depth 2 1/4" Centre to 18" at sides x 3/8" plate

Top bars 4" x 3" x 1/2" double (4" bearing surface)

Bottom bars. 3" x 3" x 3/8" double

Spacings at ends 15" x 8" x 7/16"

No. 1. Hatch 3 beams spaced 6' 3" apart (maximum)

No. 2 " 4 " " 6' 1 1/2" " "

Bearing of hatch beams 3"

Y. A. Simpson

Surveyor to Lloyd's Register  
Liverpool 9<sup>th</sup> Sept 1949.

RETAIN

M. J. [Signature]

20 SEP 1949

