

Rpt. 13.

Received at London Office

19

REPORT ON ELECTRIC LIGHTING INSTALLATION. No. 4243

Port of *Philadelphia* Date of First Survey *13-1-21* Date of Last Survey *29-9-21* No. of Visits *48*
 No. in Reg. Book on the ~~Iron~~ *Steel* *S. Agwimex* Port belonging to *New York*
 Built at *Chester Pa* By whom *Sun Shipbuilding Co* When built *1921*
 Owners *Atlantic Gulf & West Indies S.S. Lines* Owners' Address *New York*
 Yard No. *41* Electric Light Installation fitted by *Sun Shipbuilding Co* When fitted *1921*

DESCRIPTION OF DYNAMO, ENGINE, ETC.

Two (2) G.E. Compound wound continuous current generators direct. Connected to two G.E. vertical Engines

Capacity of Dynamo *174* Amperes at *115* Volts, whether continuous or alternating current *Direct*
 Where is Dynamo fixed *Platform up in Engine Room* Whether single or double wire system is used *Double*
 Position of Main Switch Board *Port side Dynamo Room* having switches to groups *Screw* of lights, &c., as below
 Positions of auxiliary switch boards and numbers of switches on each *one six circuit-panel in Dynamo Room*
one eight circuit-panel in Engine Room hatch, one six circuit-panel in Bridge Deck house. Junction boxes outside Pump Room
 If fuses are fitted on main switch board to the cables of main circuit *Yes* and on each auxiliary switch board to the cables of auxiliary circuits *Yes* and at each position where a cable is branched or reduced in size *Yes* and to each lamp circuit *Yes*
 If vessel is wired on the double wire system are fuses fitted to both flow and return wires or cables of all circuits including lamp circuits
 Are the fuses of non-oxidizable metal *Yes* and constructed to fuse at an excess of *100* per cent over the normal current
 Are all fuses fitted in easily accessible positions *Yes* Are the fuses of standard dimensions *Yes* If wire fuses are used are permanent instructions fitted on or near each switch board giving particulars of proper size of fuse for each circuit *Yes*
 Are all switches and fuses constructed of incombustible materials and fitted on incombustible bases *Yes*

Total number of lights provided for arranged in the following groups:—

Group	Description	Number of Lights	Wattage per Light	Total Wattage	Total Current (Amperes)
A	Bridge House	52	32	1664	20
B	Afters Quarters	54	32	1728	20
C	Cong. Boiler Room	62	32	1984	22
D	Deck & Forecastle	28	32	896	15
E	Pump Room	16	32	512	7
1	Mast head light with 2 lamps each of	2	40	80	1
2	Side light with 2 lamps each of	2	40	80	2
6	Cargo lights of 36 @ 32	36	32	1152	Incandescent

If are lights, what protection is provided against fire, sparks, &c. *None used*
 Where are the switches controlling the masthead and side lights placed *on Tell. Tale panel in Pilot House*

DESCRIPTION OF CABLES.

Main cable carrying *142* Amperes, comprised of *2* wires, each *000* S.W.G. diameter, *0.132* square inches total sectional area
 Branch cables carrying *22* Amperes, comprised of *2* wires, each *30000* CM S.W.G. diameter, *0.0260* square inches total sectional area
 Branch cables carrying *20* Amperes, comprised of *2* wires, each *30000* CM S.W.G. diameter, *0.0260* square inches total sectional area
 Leads to lamps carrying *4* Amperes, comprised of *2* wires, each *4000* CM S.W.G. diameter *0.00323* square inches total sectional area
 Cargo light cables carrying *2* Amperes, comprised of *2* wires, each *1620* CM S.W.G. diameter *0.00128* square inches total sectional area

DESCRIPTION OF INSULATION, PROTECTION, ETC.

All lead and Armored cable used throughout. Ship stuffing tubes used going through bulkheads: Lead bushings used going through beams & water-tight features used
 Joints in cables, how made, insulated, and protected *All joints made mechanically tight then soldered and wrapped with rubber and linen tapes*

Are all the joints of cables thoroughly soldered, and the flux used not containing acids or other corrosive substances *Yes* Are all joints in accessible positions, none being made in bunkers, cargo spaces, or spaces which may at any time be used for carrying cargo, stores, or baggage *No*
 Are there any joints in or branches from the cable leading from dynamo to main switch board *No*
 How are the cables led through the ship, and how protected *Strapped to decks and pans made for that purpose*



002051-002061-0101

DESCRIPTION OF INSULATION, PROTECTION, ETC.—continued.

Are they in places always accessible Yes

What special protection has been provided for the cables in open alleyways or where exposed to weather or moisture Lead & armored cable used and water-tight fittings

What special protection has been provided for the cables near galleys or oil lamps or other sources of heat Lead & armored cable

What special protection has been provided for the cables near boiler casings Lead & armored cable

What special protection has been provided for the cables in engine room Lead & armored cable

How are cables carried through beams Leaded bushings through bulkheads, &c. Lead bushings

How are cables carried through decks Lead & armored cable in conduit pipes

Are any cables run through coal bunkers No or cargo spaces No or spaces which may be used for carrying cargo, stores, or baggage No

If so, how are they protected ✓

Are any lamps fitted in coal bunkers or spaces which may at times be used for cargo, coals, or baggage ✓

If so, how are the lamp fittings and cable terminals specially protected ✓

Where are the main switches and fuses for these lights fitted ✓

If in the spaces, how are they specially protected ✓

Are any switches or fuses fitted in bunkers No

Cargo light cables, whether portable or permanently fixed Portable How fixed Extension cord

In vessels fitted on the single wire system, how is the dynamo terminal fixed to the hull of vessel ✓

How are the returns from the lamps connected to the hull ✓

Are all the joints with the hull in accessible positions ✓

Is the installation supplied with a voltmeter Yes and with an amperemeter Yes, fixed on Switchboard

VESSELS BUILT FOR CARRYING PETROLEUM.

In vessels built for carrying petroleum, are all switches and fuses fitted in positions not liable to the accumulation of petroleum vapour or gas Yes

Are any switches, fuses, or joints of cables fitted in the pump room or companion No

How are the lamps specially protected in places liable to the accumulation of vapour or gas Vapor proof fixtures

The copper used is guaranteed to have a conductivity of not less than that of the Engineering Standards Committee's standard, and the wires are protected by tinning from the sulphur compounds present in the insulating material.

Insulation of cables is guaranteed to have a resistance of not less than 600 megohms per statute mile at 60° Fahrenheit after 24 hours' immersion in water, the test being made after one minute's electrification at not less than 500 volts and while the cable is still immersed.

The foregoing statements are a correct description of the Electric Light installation fitted by us on this vessel and we declare that it is at this date in good order and safe working condition.

A.A. Howitz

Electrical Engineers

Date 3-10-21

COMPASSES.

Distance between dynamo or electric motors and standard compass 250 ft.

Distance between dynamo or electric motors and steering compass 250 ft.

The nearest cables to the compasses are as follows:—

A cable carrying	$\frac{1}{2}$	Amperes	1	feet from standard compass	1	feet from steering compass
A cable carrying	$\frac{1}{2}$	Amperes	3	feet from standard compass	6	feet from steering compass
A cable carrying		Amperes		feet from standard compass		feet from steering compass

Have the compasses been adjusted with and without the electric installation at work at full power Yes

The maximum deviation due to electric currents, etc., was found to be Nil degrees on all course in the case of the standard compass and Nil degrees on all course in the case of the steering compass.

A.A. Howitz

Builder's Signature.

Date 3-10-21

GENERAL REMARKS.

This installation has been well fitted on board vessel and proved satisfactory under full trial

It is submitted that this vessel is eligible for THE RECORD.

Elec. Light. 24

2/11/21.

Ans. J. Adamson

Surveyor to Lloyd's Register of Shipping.

2in. 11, 19—Transfer.

Committee's Minute

New York OCT 11 1921

Elect light



© 2020

Lloyd's Register Foundation

THE SURVEYORS ARE REQUESTED NOT TO WRITE ACROSS THIS MARGIN.