

"KYANITE"

- (1) Hatch covers renewed as necessary.
- (2) Two hatch webs in each hatchway renewed  
.35 plate with 4 x 3 x .42 top angles  
and 3½ x 3 x .42 bottom angles.
- (3) Air pipes fitted with canvas covers.
- (4) Freeing port area in the R.Q.D. bulwarks  
increased to 19¾ square feet by three additional  
ports 2'9" x 1'6" each side 7'8", 29'9" and 39'7"  
from R.Q.D. end fitted with bars.

----- 000 -----



© 2020

Lloyd's Register  
Foundation

002062-002070-0164

