

7 APR 1952

Lloyd's Register of Shipping.

Ship's Name "JALAGOPAL"

Official No. 129544.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines.

Particulars of CompanionwaysOn Shade Deck

- 1) Forward of N^o 1 Hatch, 6'-6" x 5'-9" opening in deck protected by substantially constructed steel house fitted with 2 hinged steel doors, 5'-0" x 2'-6" with 12" coaming, operable from both sides.
- 2) Forward beam space of N^o 2 hatch permanently closed & fitted with substantial teakwood companion house having 2 double hinged teakwood doors, 5'-7" x 4'-4" with 12" coaming, operable from both sides.
- 3) Aft of N^o 2 Hatch, 6'-6" x 7'-0" opening in deck protected by substantially constructed steel house fitted with 2 hinged steel doors, 5'-3" x 3'-0" with 12" coaming, operable from both sides.
- 4) Forward beam space of N^o 3 Hatch permanently closed and fitted with substantial teakwood companion house having 2 double hinged teakwood doors, 5'-8" x 3'-10" with 12" coaming, operable from both sides.
- 5) Aft of N^o 3 Hatch, 6'-3" x 6'-10" opening in deck protected by substantially constructed steel house fitted with 2 double teakwood doors, 6'-3" x 5'-2" with 12" coaming, operable from both sides.

On Upper Deck

- 6) To N^o 3 Tween Deck - 1 Companion (p+s) openings in deck 3'-7" x 5'-11" protected by steel casing fitted with hinged teakwood doors, 5'-5" x 2'-9" with 9" coaming, operable from both sides.
- 7) To N^o 4 Tween Deck - 1 Companion (p+s) openings in deck 3'-7" x 5'-11" protected by steel casing fitted with hinged teakwood doors, 5'-1" x 2'-10" with 14 1/2" coaming, operable from both sides.
- 8) Forward of N^o 3 Hatch, deck openings 5'-0" x 2'-7" (p+s) protected by steel casing fitted with hinged teakwood doors 5'-2" x 2'-4" with 12" coamings, operable from both sides.

Ventilators

- On Fore Deck :- 3 @ 7 1/2' diameter 36" x 25" coaming - cowl vents.
 4 @ 9" " 32 1/2" x 25" - - M.V. with S.D. tops.
- On After Deck :- 2 @ 12" " 36" x 31" " - Cowl vents.
 5 @ 8" " 30" x 31" " - M " "
 1 @ 8" " 19" x 31" " - M.V. with S.D. top.

All cowl ventilators supplied with wood plugs & covered covers.

Coaling Ports

Seven 2'-10" x 2'-5" coaling ports (p+s) to ellain Tween Decks fitted with substantial hinged steel covers secured by bolted strongbacks.

(Please see continuation sheet)

J. S. Mathin 20th March, 1952.

Lloyd's Register of Shipping.

Ship's Name "JALAGOPAL"

Official No. 129544.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines

HatchwaysOn Shade Deck

N^o 2 Hatch :- Effective length was 21'3" on account of fitting of companion in item 2) on Sheet 1. Fore end of hatch battened by means of 24" spaced cleats bolted to teakwood companion house.

N^o 3 Hatch :- Effective length was 21'3" on account of fitting of companion in item 4) on Sheet 1. Battening arrangements as for N^o 2 Hatch.

On Upper Deck

N^o 2 Hatch :- Forward beam space closed permanently to form Companion^{ing} landing -- effective length was 21'3". Fore end of hatch battened by means of cleats formed by angle lug toe welded to standing flange of hatch beam, spaced approx. 24" cr. to cr.

N^o 3 Hatch :- As for N^o 2 Hatch - details above.

A copy of this Report has been placed on board the vessel.

H. J. Gathin
Vizagapatam, 20th March, 1952.

Nalin A. R.
23.4.52