

COPY.

REGISTER
NEWCASTLE-ON-TYNE

(5.3.25.)

ASCANIA PROPOSAL AGREED TO PROVIDED DECK GIRDER BE FORMED OF
POINT FIVEFOUR VERTIEAL PLATING WITH TWELVE BY THREE AND HALF
BY THREE AND HALF BY POINT SEVEN NOUGHT DOUBLE CHANNELS AND EIGHT
BY POINT SEVEN NOUGHT RIDER PLATE THE FACE BULB ANGLES ON THE
WEB AT BULKHEAD ONE FOUR NINE BE EIGHT BY THREE BY POINT FOUR FOUR

AND WEB OF PILLAR ON FRAME ONE FIVE SEVEN BE ADDITIONALLY
SUPPORTED BY ANGLE STIFFENER.

COMMITTEE FEN.



© 2020

Lloyd's Register
Foundation

002079-002084-0063