

T.S.S. "ASCANIA"

Proposed Conversion of Deep Tank for Carrying
Fresh Water.

The Southampton Surveyors have forwarded an outline plan showing the general arrangements as proposed and state that structural plans of the new bulkheads will be submitted in due course.

It is submitted the Surveyors be informed that if the tanks will not be used partially filled it will not be necessary to fit wash plates. It will be necessary however, if any of the tanks on one side of the centre line bulkhead are empty while the tank or tanks on the other side are full, for the scantlings and arrangements of the centre line bulkhead to be made equivalent to the requirements of Section 19 of the Rules for boundary bulkheads.

It is assumed that oil fuel will not be carried in the double bottom tank in way of the fresh water tanks when fresh water is carried in the latter.

that the pumping arrangements will be such that contamination of the Fresh Water is impossible.

Return plan

JD

13.11.42

JD



© 2020

Lloyd's Register
Foundation

002079-002084-0092