

Lloyd's Register of Shipping,

9, Eden Quay,

Dublin, 8th February 1933.

LLOYD'S REGISTER
RECEIVED

-9 FEB 1933

LONDON

Enclosure

Dear Sir,

I beg to enclose herewith Freeboard Report of survey held on the steamer "J. F. V." No 64686 in the Register Book.

With regard to the moulded displacement etc. particulars are not available at this port.

The following items require attention.

1. Stiffeners on No 1 and 2 hatch coamings require renewal.
2. No 1 hatch covers (wood) forward section have at present an unsupported length of 8 feet.
3. Starboard fiddley stowhold ventilator coaming thin, to repair. The coamings of the 8" ventilators leading to the holds are thin. The Owners representative suggested that he might do away with these ventilators and fit riveted plates on deck in way of same, as he considered that the large ventilators fitted for cattle give ample ventilation to the holds.

J. F. V. CONTINUED.

4. Fiddley casing top in way of funnel to repair.
5. Galley skylight. aft. companion wood covers to repair, coaming & ledge bars forward stow companion to repair.
6. all door handles & locks in way of openings to repair.
7. all defective hatch covers to be repaired or renewed as required.

I am, Dear Sir,

Yours faithfully.

R. B. Guer.

The Secretary

London.



© 2020

Lloyd's Register
Foundation

002079-002084-0141

Referred to the Chief Ship Surveyor.
(Freeboard).

[Handwritten signature]

- 9 FEB 1933

[Faint, mostly illegible handwritten text, possibly bleed-through from the reverse side of the page]



© 2020

Lloyd's Register
Foundation



MS. REG