

Lloyd's Register of Shipping.

Ship's Name LANRICK

Official No. 142020

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in APRIL, 1932.

There are hinged steel doors of substantial construction in
the sides of the trunked coal hatch in bridge tween deck space.
Sills to door are 24" high.

The scantlings of the machinery casing in bridge tween deck
space are plating .25", coaming .30", stiffeners 3x2½x.32 O.A.
(no brackets) spaced 30"/29". There are no openings in the
machinery casing. (Cls. May, 1938).

