

002094-002100-0096

A 3m,7.51.

## FREEBOARD REPORT on the "HOI HUNG" (Ex "FIONIA").

It is submitted the Freeboards given on the accompanying form, being those ~~as previously assigned by Danish authorities~~ <sup>as previously assigned by Danish authorities</sup>, merit approval, the same to be marked on the vessel's sides, inserted in the certificate of classification, and recorded in the Register Book. Subject to

- 1) Vents to Silencer Room & E. Run over 36" in height being suitably supported ~~that in the fore (PS) was machy. casing (P.S.)~~
- 2) ~~Door Coaming of Companionway Poop (P.S.) being 24" in height.~~
- 3) ~~Bridge Deck Machinery vents being of the screw down w.i. type. the Fello & Poop Deck Greenneck vents being 36" in height.~~
- 4) ~~Exhaustation deck Air pipes on superstructure decks being 18" in height to opening~~
- 5) ~~Height on poop being 18" in height to lowest point of opening~~
- 6) ~~Freeing Port was in forward well being at least 24" x 24"~~
- 7) ~~Escape hatch on FPA Deck & access hatch on Forecastle both coamings being increased to 24" in height and access hatch Coaming on Bridge Deck being increased to 18"; alternatively notices should be displayed on each cover to the effect P.T.O.~~



"Cover to be kept closed whilst at sea".

The Surveyor should be requested to report the positions of the funnels now reported, i.e. on which deck & means of closing & position of 3' 0" dia. funnel.

The Surveyor should note that freeboards are marked from 2 1/2" wood deck and not 3".

(Return plans to Records).

Steel bands on hatch covers.



© 2020

Lloyd's Register  
Foundation

1884  
26/4  
LC