

PRELIMINARY FREEBOARD PARTICULARS.

Builders Dimensions :- 280'0" B.P. x 41'6" ext. x 22'3" moulded.

Length on L.W.L. :- 279'6".

Sheer at stem :- 8'0". = (7'3" + 9")

" " <sup>abaft</sup>  $\frac{1}{8}$  L./stem :- 4'1".

" "  $\frac{1}{8}$  L. before stern :- 3'1".

" " stern. :- 5'6".

*Smiths Dock Co. Ltd.  
Southampton.*

Approximate under deck tonnage. 1882.

Displacement co-efficient B.K. .76.

Approximate Tons per inch .. 22.7

Breadth at Upper Deck Gunwale. 39'11".

Round of beam. 10".

Upper deck not covered with wood, except amidships in way of accommodation.

Peep 22'7 $\frac{1}{2}$ " x 7'3".

Bridge 48'7" x 7'3".

Forecastle 23'3 $\frac{1}{2}$ " x 7'3".

Freeing port area in wells to rule.

Engines amidships.

Bridge front of steel without openings.

Bridge end of steel with openings and weatherboards fitted.

Forecastle front of steel with openings and weatherboards fitted.

Peep front of steel without openings.

Crew berthed in peep.



© 2020

Lloyd's Register  
Foundation

002119-002126-0092