

COPY

# Lloyd's Register of Shipping,

ENCLOSURES

High Close, Wokingham, Berks.

14th January 1944

P. Dear Sir,

I duly received your letter of the 7th instant respecting the "LADY CONNAUGHT" and in reply I have to say that the scantlings are such that a moulded draught of 17' 0" could be permitted. The following scantlings are suggested for the additional structure used for filling in the wells:-

Side Shell	.44
Deck	.56 if sheathed
	.30 unsheathed

with beams on every frame.

Adequate scarphing arrangements should be provided at the junction of the bridge and lengthened forecastle, the hinged doors should be watertight and of substantial construction and the strength of the structure maintained in way of the openings by suitable doubling plates.

An assignment letter is enclosed together with the plans of midship section and profile and decks.

I am, Dear Sir,  
Yours faithfully,

The Secretary,

pro Clerk to the

© 2020

Lloyd's Register  
Foundation

002157-002156-0178