

Lloyd's Register of Shipping.

Ship's Name "LAOY CONNAUGHT"

Official No. 132019.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

Hatchways. No 2 on upper deck now 10 ft. x 12 ft. ✓

Yid dley. new engine room skylight of steel strongly constructed.

Ventilators, new to holds and cattle decks.

2 No. on Forecastle coaming 2'6" dia. 2'9" x 4" thick standing on trunk 3'6" x 3'6" x 25" to No 2 hold.

2 No. in way of bridge " 2'6" " 2'9" x 4" " " " " " do.

Stokehold 2 No. " 2'6" " 5'4" x 4" " to stokehold.

2 No. on Boat deck " 2'6" " 4'8" x 4" standing on trunk 3'6" x 3'6" x 25" to tween decks.

2 " " " " 2'6" " 3'3" x 4" " " " " to No 3 Hold.

2 " " Poop " 2'6" x 5' x 4" " " " " do.

The ventilator trunks have been fitted with dampers and electric fans. They are efficiently constructed and running to rule. The Cowls are closed with 1" mesh grid and canvas covers. The ventilators not disturbed have wood plugs and canvas covers. ✓

Gangways.

Bridge deck forward side doors fitted as shown and amended on Plan. Cattle walks at the fore and aft end of Machinery casing doors 3'6" wide 6' high sill 9" with hinged sill 18" and steel hinged watertight doors fitted.

Scuppers. Fitted as shown on plan with G.M. non return storm valves fitted to side plating.

Side scuttles. All below foreward deck closed with riveted spigot patches. ✓

Superstructures. Bridge bulkhead forward fitted with hinged steel door P.S. 38, thick with stiffeners 3" x 3" x 3/8" fastened as per plan with 9" fixed coaming T hinged sill secured with clips. Steel doors P.S. fitted with hinged steel doors capable of being closed and secured from both sides of the bulkhead.

Bridge bulkhead fitted aft on frame 39 plating 3 stiffeners 4" x 3" x 35" spaced average 31" openings closed with 4" shifting boards in channels to the full height of the opening as shown on plan.

Poop bulkhead door on starboard side plated over, there is now no opening in this bulkhead.

Bulkheads. above tunnel No 3 hold on frame 55 aft removed as on plan.