

N,V.De Haan & Oerlemans, Hensden.

Yard No.274.

by Chief Ship Surveyor

Received from Chief Ship Surveyor

GB

SHIP NAME Sin.Sc.m.s. "LISBETH M"

REPORTS

(Lon.

No. 128193

(Rot.

37158

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.)

L. 199.6' B. 33.0' D. 15.08' to U.Dk. Proportions 13.25
18.73' to R.Q.Dk.

This ship was examined afloat by the LONDON Surveyors (11,53) on account of damage stated sustained as the result of an explosion in the auxiliary lighting accumulator compartment and slight indentation of aft end of E.R. light and air casing also slight distortion of the boat deck plating reported.

Owing to the minor nature of the damage no recommendations were made.

The scantlings and arrangements, as reported, conform with the Society's Revised Rules and Regulations, and are in accordance with or equivalent to those shown on the approved plans.

IT IS THEREFORE SUBMITTED the ship is eligible to be classed:-

- ✓ *100A1
- ✓ 1 Dk "pt Elec. welded"
- ✓ Cell DB 129' 230t; Side tanks in mchy space O.F; Twn. dk tank amids 8' 20t; FPT 96t; APTs pt W.B. 4lt pt F.W. pt O.F.
- ✓ FK; 3BH; Lloyd's A & CP
- ✓ P 51' Q 66' F 31'
- ✓ Mchy Aft
- ✓ O.L. 218.1'
- ✓ ESD
- ✓ Radar
- " "

REVISED CERTIFICATE



INSERT FN 2.R.L.

(Bottom in mchy space to be examined internally annually (cement omitted))

IT IS FURTHER SUBMITTED the Surveyors be requested to confirm -

- (1) the length of the forecastle as measured in accordance with the "Instructions to Surveyors" is 31' and not 23.4' as reported,
- (2) the bracket floors at the middle line and at the margin are 7.5 and 8 mm respectively as shown on the "as built" Midship Section and not as reported,
- (s) that "FERBITE" is an approved composition.

11.1.54

00265-002173-0030

© 2020 Lloyd's Register Foundation