

All alterations in the existing records should be underlined.
If the Vessel has Water Ballast Tanks, state whether the manhole covers have been removed, and the insides of the tanks
Also state the amount of deterioration (if any) found in the thicknesses of the floors, framing, girders, and of the inner
plating, especially in the boiler space.

Date of last Survey and of
Periodical Surveys.

Report, No. _____ Port _____

Fitted for Oil

"LEONARDO DA VINCI"

Bom. 7062

assigned as
now verified

IT IS SUBMITTED the NEW YORK & BALTIMORE Surveyors
be furnished with a copy of the BOMBAY Report No.7062, the
Drillings and the Interim Certificate attached thereto.

It is further submitted the BALTIMORE Surveyors be
informed by cable as follows:-

77533 CITY LINE REQUEST CLASSIFICATION STOP
BOMBAY SURVEYORS REPORT GENERAL EXAMINATION
HELD PLATING DRILLED CABLES RANGED 225 FATHOMS
2-1/8" DIA AND NO MAJOR HULL REPAIRS NECESSARY STOP
~~FOR~~ CLASSIFICATION REQUIREMENTS FOR VESSELS NOT
BUILT UNDER SURVEY TO BE COMPLIED WITH AND SPECIAL
SURVEY NO.3 TO BE HELD STOP SCANTLINGS OF VARIOUS
PARTS TO BE ASCERTAINED & FORWARDED WITH PARTICULARS
OF EQUIPMENT ON FIRST ENTRY ~~TO BENNETT STOP~~ TO BENNETT STOP
NO PLANS AVAILABLE HERE.

SGR 11-3-43

4600-361200-0094
002184-002193-0094

3

Machinery Items passed for survey at Bombay
sea connections, screw shafts, thrust & intermediate
shafts, condenser, steam pipes, oil cooler, ~~dynamos~~
screw turbines, pumps, oil fuel arrangements & the electrical
equipment in machinery spaces, officers & crew's quarters.
To complete the Classification survey all other survey
equipment to carry out, the Boilers & Superheaters, electrical
equipment & pumping arrangements to be compared with
Rules reported on first entry forms, the main turbines
to be rebladed, automatic feed regulators fitted to water
tube boilers, Scotch boiler parts retubed & fitted with
safety valves which comply with Rules, dynamo exhaust
piping to be modified & Boiler room pumping arrangements
made accessible & the fire extinguishing appliances
augmented if necessary. Sizes checked at Bombay were
screw shafts 13 3/4 fitted with jointed lines & main screw shafts 14 3/16

Requirements.

Gen. Exam 350/-
Condition 135/-
Load Line Survey 600/-

Fees applied for,
3-10-1943

Lloyd's Register
Foundation