

25 AUG 1947

by Chief Ship Surveyor

Received from Chief Ship Surveyor

SHIP'S NAME

ARMILIA

REPORT

Sld.

No. 34722

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

(The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement." - Extract from Sub-Committee's Report, 24/5/42.)

For conditions of class see previous endorsement.

ACTION is DEFERRED for repairs.

Plans showing a proposal to replace the entire structure forward of the cross bunker with new construction and at the same time introduce one extra tank (increasing the length by 32') were approved in this Office (see endorsement dated 16.5.46).

The SUNDERLAND Surveyors now report (Rpt. 8 & F.E. Report) this tanker placed in dry dock and bottom coated.

A new portion forward of the cross bunker constructed, and connected to existing after part, and an extra tank introduced, increasing the length of the vessel as stated above.

*Copy in copy sent to Basement to await reports*

A PERIODICAL SPECIAL SURVEY (C) (vessel 16 years old) was held on the existing after portion of vessel, and repairs effected to shell and deck plating, aft peak tank and pump room, etc.

Due to damage by grounding and collision etc. repairs and renewals effected to sternframe, rudder mainpiece, keel and shell plating etc.

The equipment originally in excess of Rule requirements has been accepted for the increased dimensions (see endorsement referred to above).

It is submitted the vessel is worthy to remain as classed, with record of docking survey 7.47 and notation of 'S.S. Sld. - 7.47' assigned as recommended, without special condition.

7.47 Sld. )  
'S.S. Sld. - 7.47' ) without

Insert in R.B: Len. & renewed for'd of cross bunker '47.  
O.L. 349'  
pt. Elec. welded



© 2020

Lloyd's Register  
Foundation

P.T.O.

002206-002214-0161 2

"ARMILLA"

Amend R.B:

(Equipment) t2"

to u2"

Longitudinal framing  
at bottom & at deck

to

Longitudinal framing at bottom  
and ~~at~~ trunk top ~~and sides~~ in  
centre tanks

Trunk 169'

to

trunk 201'

11BH

to

12BH

FPT 52t

to

FPT 48t



© 2020

*J. McC*

18-8-47

*6/11/47*

Lloyd's Register  
Foundation

002206-002214-0161 <sup>2</sup>/<sub>2</sub>