

Copy sent to Owners
7/1

7 JAN 1957

308-7

Rpt. C. 11 (Contd.)

Index No.

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

FB 538

Ship's Name "BOSCHKERK" ex "BOSCHFONTEIN" Official No. -

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in Amsterdam

Alteration hatchway IV on C deck

Size: 2225 x 1766 6553 x 5791mm - size as original construction plan.

Height above steel deck: 370mm ✓

Coaming: 300 x 15

Spacing of cleats: 145mm - closed as before.


Shelter deck

Freeboard

Alteration hatchway IV on D deck

Casing port, starboard and aft removed and flush coaming made

was per sketch 30 beam



New hatchways made port and starboard on poop deck: frame 2-8

Size: 3550 x 2000

Height above steel deck: 450 mm

Coaming: 11mm

Thickness of hatches: 83mm - fitted with galvanized steel endbands

Bearing surface: 76mm

Spacing of cleats: 155mm

Tarpaulins: 2

Amst. 7.1.

Ditto on Shelterdeck aft:

Size: 3550 x 2130

Height above steel deck: 230mm

Coaming: 230 x 12

Thickness of hatches: 83mm - ~~not~~ fitted with steel endbands

Bearing surface: 75mm

Spacing of cleats: 155mm

Tarpaulins: 2

Signature

(E.D.H.F. Pronker)

Refust & Plane

2/1



© 2021

Lloyd's Register
Foundation

002222-002228-0170