

23 MAY 1947

Lloyd's Register of Shipping.

Ship's Name "K E N T".

Official No. 142611.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

Alterations:- Additional accommodation fitted at after end of bridge tween decks (PS).

Steel bulkheads in bridge tween decks fitted round same.

Port side tonnage opening in bridge end plated over and new opening 4.1' x 3.1' with 20" coaming cut in bridge end nearer centre line, closed by portable steel plate secured with hook bolts not less than 12" apart.

Side light with hinged deadlights of substantial construction fitted in bridge tween deck shell.

A Steel companionway of strong construction built on bridge deck for access to accommodation with 15" coaming and closed by 2" hinged wood door operated from both sides.

2 - 8" diameter vents 36" high and 3 - 6" G.N. Vents 24" high fitted in bridge deck and fitted with satisfactory closing appliances.

Bridge deck hatchways (to old bunker spaces) in port and starb. alleyways removed and openings efficiently plated over.

Intd. #
23 MAY 1947

W A Robinson

SURVEYOR TO LLOYD'S REGISTER.

Liverpool 4/47.

Copy of above placed on board vessel.

W A R



© 2020

Lloyd's Register
Foundation

002260-002268-0012