

13 MAY 1948

Rpt. C. 11 (Contd.)

Index No.

Lloyd's Register of Shipping.

Ship's Name "MATAROA"

Official No. 144814

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

ALTERATIONS:- The following alterations noted on request of Owners' representative -

COMPANIONWAYS:- fitted on Nos. 2, 5 & 6 upper deck hatchways on instructions of the Ministry of War Transport for access for forces personnel to accommodation in Nos. 2, 5 & 6 'tween decks, one at each side of each of above hatches, strongly constructed of steel, secured to after end coaming and 1 hatch beam by E.W. (hatch beams bolted in place).

Openings in companionways at No. 2 & 5 Hatchways 5'3" x 3'9"; sill 33" above deck.

Openings in companionways at No. 6 hatchway 4'3" x 3'9"; sill 33" above deck.

Openings closed by hinged wood doors, capable of being operated from both sides and companions fitted with angles E.W. to front forming channels and 2½" stormboards and tarpaulins, cleats and battens for battening down.

Suitable arrangements also made for battening down main hatches in way of companions.

Cancelled

Geo. Cockburn
Lloyd's Register
Foundation
Glasgow 16/3/42.

002269-002278-0138