

m.v. "ST. EUSTATIUS"

Rpts. Cco. Nos. 2090 & 2168.

This ex German vessel was built in 1921 under the supervision of the Bureau Veritas and subsequently classed with the Germanischer Lloyd.

The new Owners desire classification with this Society.

The vessel is to be used for service between Curacao and Aruba for the transport of sulphuric acid carried in four large cylindrical tanks installed in the holds.

Plans and particulars, embodying alterations for the special service, forwarded by the Curacao Surveyor through the New York Office, have been examined and the scantlings and arrangements found suitable for the class 100A- "For Service between Curacao and Aruba" "Carrying sulphuric acid in portable cylindrical tanks" (see endorsement and correspondence attached).

A First Entry Report and Rpts. 8 have also been received.

The vessel placed in dry dock, bottom coated, the scantlings and arrangements verified and the requirements of a 2nd S.S. No. 3 complied with.

The shell plating has been drilled with results which appear to be satisfactory.

The upper deck has been completely renewed from stem to after cargo hatchway with openings arranged to suit present requirements. Renewals or repairs to shell plating, framing, bulkheads, poop deck, tank margin plating, fore peak tank top, chain locker, mast, steering arrangements, air and sounding pipes etc. effected.

Three portable cylindrical acid tanks have been fitted in the forward hold and one in the after hold as indicated on the approved plan. Two portable oil fuel tanks have also been fitted in the after hold. These tanks have been tested and found satisfactory.

The Surveyor states that an equipment in accordance with letter "g" has been ordered. When this has been supplied the figure "1" can be assigned.

P.T.O.



© 2020

Lloyd's Register  
Foundation

002279-002280-0052 2.

special arrangements are made for  
securing the tanks in position.

It is submitted the vessel is worthy to be classed  
100A- "For Service between Curacao and Aruba" "Carrying sulphuric  
acid in portable cylindrical tanks" with record of docking survey  
10.41 and notation of S.S. 2nd No.3- 10.41.

100A- "For Service between Curacao and Aruba"  
"Carrying sulphuric acid in portable cylindrical tanks".

10.41 Cco.

S.S. Cco. 2nd No.3-10.41

1 Dk

Cel DB 100' 143t, FPT 18t, APT 6t

FK, 4BH, Cem

P & B 60' F 14'

Mchy Aft

O.L. 148.2

002279-002288-00522

