

NOS. 573 - 4 - 5.

PROVISIONAL FREEBOARD PARTICULARS.

Length on load waterline	...	...	529.33'
Breadth extreme	...	...	68.27'
Depth moulded to "C" (Upper) Deck	...	...	35.5
Depth of Hold (to top of ceiling excluding grounds)	...	...	31.20
Framing	...	...	Depth 12" and 9".
Round of Main	...	...	Nil.
	"C" Deck	...	6"
	"B" Deck.	...	Level.
Camber of Tank	...	...	6" x 2"
Cargo Battens	...	...	2½" thk. on 2" Grounds.
Ceiling	...	...	67.85
Breadth Amidships on "C" (Upper) Deck..	...	...	

Sheers.

Sheer forward above midships "C" Deck.	9.5
" Aft " " "	4.75
Sheer at 1/8 length from F.P.	5.22
Sheer at 1/8 length from A.P.	2.61
Note:- Lowest point of sheer is amidships.	

Erections.

	<u>Length.</u>	<u>Height.</u>
Complete Superstructure to "B" (Shelter) Deck ...	Whole length of vessel.	8'-6" at centre 8'-0" at sides.
Forecastle on "B" (Shelter) Deck, Open end ...	77.5	8'-0"
Bridge on "B" (Shelter) Deck, Weather-tight doors fitted at Forward and after ends.	205'-0"	8'-6"
Tonnage under deck ...	about 9,295	
Registered dimensions:-	Length.	540.25
	Breadth.	68.27
	Depth.	31.20

Freeing Port Area - No bulwarks fitted.

Hatches.	18.0 x 16.0	} Forward.
	34.66 x 18.0	
	26.66 x 16.0	
	24.0 x 16.0	} Aft.
	24.0 x 16.0	
	24.0 x 16.0	

© 2020

Lloyd's Register  
Foundation

002289-002297-0220