

BRISTOL

July 19th, 1922.

S.P. Dorey

The Managing Owners Representative attend on board the Roumanian Steamer "EMIL GEORG V STAUBS", No. 14991 in the Register Book, on the 12th July 1922 and subsequent dates, with a view to examining both main boilers.

The port and starboard main boilers were examined internally and externally and several boiler tubes in all the back ends found choked with salt and all the furnaces distorted.

All choked tubes have been cleared and about 25 per cent of the tubes expanded. On account of the distortion of the furnaces the boiler pressure has been reduced to 180 pounds per square inch and the safety valves of both boilers adjusted to this pressure, and these boilers appear to be in a fit condition to enable the vessel to proceed to the Tyne, where it is stated, they will be further examined and repaired.

SURVEYOR TO LLOYD'S REGISTER OF SHIPPING.



002305 - 002319 - 0018

© 2020

Lloyd's Register  
Foundation