



Lloyd's Register of Shipping,

RECEIVED

4 SEP 1947

ANSO.....

P.O. Box 701, Westerkade 5b

Rotterdam, 2nd. September, 1947.

ications to be addressed to
SURVEYORS

e:

Dear Sir,

In reply to your letter of the 7th. August, 1947, regarding the m.v. " ELISABETH " Rot.Report No. 99578, I beg to state that the water ballasttank as referred to has been examined internally and found in good condition. ✓

The tank, however, is not used as ballasttank and is only connected with a handpump for draining. ✓

The capacity of same is 3 tons. ✓

The scantlings and spacing of the stiffeners of the after peak are correct; I may, however, observe that the flare of the shell at that part of the vessel is such that the length of stiffeners exceeds nowhere 2,00 mm. ✓

The spacing of 750mm in my report is the maximum spacing in the ships sides, the spacing of the stiffeners near the centre being 630 mm. ✓

The arrangement of pillars is as shown on the approved plans. ✓

The situation of the oil fuel tank is not in full confirmation with the approved plans, there being a clearance of about 200 mm. between the bottom of the tank and the top of the water ballasttank.

The tank is supported by beams and the sides are clear of the ships sides, reason why this tank has not been regarded as part of the ships structure. ✓

The particulars intended for insertion in the Register Book are as follows:-

length of poop	36,9	feet
length of forecastle	18,5	"
overall length	135,8	"
length forepeak tank	12,5	"
length afterpeak tank	5,-	"

The plan of the rudder is going herewith.

The results of the shell drillings are tabulated underneath.

002305-002319-0270 1/2

see continuation sheet.

Lloyd's Register
Foundation

Rotterdam, 2nd. September, 1947.

Re: m.v. " ELISABETH ", Rot. Report. No. 99578.

Drillings of shell in mm.

	<u>Middle</u>			<u>Forward</u>			<u>Aft.</u>		
	<u>Orig.</u>	<u>P.</u>	<u>S.</u>	<u>Orig.</u>	<u>P.</u>	<u>S.</u>	<u>Orig.</u>	<u>P.</u>	<u>S.</u>
Sheer strake	10	9 1/2	9	7	6 1/2	7	7	7	6
1st below	8	8	8	7	6	6 1/2	7	6 1/2	7
2nd. below	8	7	7	7	7	6	7	6	6
3rd. below	8	7	7	7	6	6	7	7	6 1/2

I regret that the items mentioned above were not clear on my report.

Yours faithfully,

J. Wiskoot

Encl.

The Secretary,
LONDON.



© 2020

Lloyd's Register
Foundation

002305-002319-0270 2/2

Referred to the D.O.

Referred to the D.O.

Rd

For Slip Surveys (P.E. Rpts.) to note

J.C.D.

Handwritten

Handwritten

ON WAY LABOR.



© 2020

Lloyd's Register Foundation