

Lloyd's Register of Shipping.

28 JUL 1943

Ship's Name "ROTA"

Official No. 113757.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in

Modifications due to crews accommodation being transferred
from Lower Deck to Deck Tween Decks.

Deck Front.

Space between aft end of paint locker, and aft end of steel
companionway on L , now plated over, on port side; and
space between fore end of steel companionway and existing
W.C. bulkhead, on starboard side, now plated over, having
strongly constructed wood door, operated from both sides.

Size of opening 5'-0" x 23"; sill 12".

4 extra side scuttles fitted in deck tween decks, (2 p. + 2 s)
each 7" diam, fitted with strongly constructed metal
headlights.

16" diam. escape scuttle fitted in deck front.

John Barnett.
Leith 24/7/1943.

Copy of above placed on board.