

Lloyd's Register of Shipping. 15 SEP 1951

Ship's Name ~~"BALTRAFFIC"~~ *Sufina e Tariq* Official No. 142597Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in -

Hatchway on bridge deck aft (s.s.) over Refrig. Evap. Compt. now removed and
aperture in deck 5'6" x 7'0" closed by plating over and re-instating wood decking
in way.

Port and starboard tonnage openings at after end of new bridge 'tween deck bunker
spaces (previously used for refrigerating plant) now closed by 1/4" steel plate
with internal boundary angle, 1 1/2" x 1/4" rubber joint and 14 - 3/4" hook bolts.

Two 24" cast iron circular screw down escape hatches have been fitted in bridge
deck at after end into new 'tween deck bunker space (p. & s.).

Port and starboard bulkheads in way of steering engine flat permanently closed
by riveted plate.

G.B. Davis for MacLeod self
Sincerely 4/9/51.



© 2020

Lloyd's Register
Foundation