

17 SEP 1947

Rpt. C. 11 (Contd.)

Index No.

Lloyd's Register of Shipping.

Ship's Name "BROUGHTY"

Official No. 144705

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in

Oil tanks forward (p. 15.) dispensed with and space
now taken into no 1 Hold.

no 1 Hatchway now 27' long - one extra hatch beam
now fitted making 4 in all - spacing 5'-5", bearing
surface 4"

top angles 5x3x.50 - web plate 13"x.34"
bottom angles 3x3x.42

additional hatch covers 2½" thick - W.W. - F. & A. - 3" bearing
spacing of cleats 21" - no of tarpaulins 3. (aft)

2- 9" diam ventilators fitted within line of hatch to no 1

Hold (1 p. 15.) coaming 36"x.32" - constructed in accordance
with the rules - with wood plugs and canvas covers.

all sounding, air & filling pipes etc to forward oil tanks
(p. 15.) now dispensed with and openings blanked off.
Plating etc on top of aft end no 1 Hatchway removed

S Bowman

15/9/47.

checked &
17 SEP 1947

MILP



© 2020

Lloyd's Register
Foundation

002340-002351-0042