

Rpt. 12.

COPY.

FREEBOARD VERIFICATION FORM FOR STEAMERS.

Port Liverpool.

When received in London Office

Vessel's Name "S A M A R I A".

Official No.

No. in Reg. Book 29756.

Port of Registry *(For Foreign Vessels)*

Iron or Steel Steel State whether Classed by Lloyd's Register (Contemp.).

Name of Owners Date of Verification 28th February, 1922.

I have to report that the Freeboard from the centre of disc to the top of the statutory deck line, and the lines in connection therewith, as given below, assigned by the Committee to this vessel, have been correctly marked on the vessel's sides, in accordance with the printed instructions:—

| | | |
|--|-----------------------------------|----------------|
| From centre of disc to top of statutory deck line | <u>13</u> ft. | <u>10</u> ins. |
| From centre of disc to top of statutory deck line } at awning or part-awning deck . . . } | <u>For all Seasons.</u> -- ft. | -- ins. |
| Fresh Water line above centre of disc . . . | | <u>8</u> ins. |
| Indian Summer line above centre of disc . . | | -- ins. |
| Winter line below centre of disc | | -- ins. |
| Winter North Atlantic line below centre of disc | <u>"D"</u> | -- ins. |
| Distance between the top of statutory deck line on vessel's side and the intersection of the continuation of upper side of wood or steel deck with the vessel's side } at main, spar or upper dk. | <u>1</u> | ins. |
| at awning or pt.-awning dk. | -- | ins. |

It should be clearly shown whether the statutory deck line is set off from a wood or steel deck.

When more than 12 passengers are carried and any are accommodated between E & F decks before and abaft the machinery spaces, the foregoing loadline shall not apply, and the maximum loadline in salt water for all seasons shall be 1'-5" below the centre of the disc.

Condition of hull

(Signed) G. L. LYLE. Surveyor.

(To be filled up in London Office.)

Statement No. Date of Committee's Minute 10. 12. 20.

| | | | |
|--|-----------------------|---------------|----------------|
| Particulars for record in Register Book. | Moulded Depth . . . | <u>45</u> ft. | <u>0</u> ins. |
| | Freeboard | <u>13</u> ft. | <u>10</u> ins. |
| | Corresponding Draught | <u>31</u> ft. | <u>8</u> ins. |

Freeboards compared and found correct by Date

Is fee paid? Form for Certificate

Instructions Date

Certificate written Noted for posting

2m, 11, 21.—T.



© 2020

Lloyd's Register Foundation

002340-002351-0167

Spacing EVERY FRAME EVERY FRAME

Tie Plates Deck, Material and thickness

28 4 2 3