

LLOYD'S REGISTER OF SHIPPING

ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name "ADVISER"

Official No. ~~50335~~ 166263

Port of Registry LIVERPOOL.

This ship has been under survey at LIVERPOOL.

on October/November 1958. and the following alterations to the conditions of assignment of loadlines have now been effected/found:—

2 Mechanical ventilation units now fitted each 22" in dia. and .40"thk.

with permanent 12" high welded coamings and 3'-6" high portable fan unit

fitted with external flanges and secured by 18 at $\frac{3}{4}$ " Dia. bolts, each ventilator

efficiently stayed and closed by wood plugs and canvas covers, with separate

cover plates .40"thk for closing ventilators when fan units are unshipped.

(When unshipped the coamings are watertight by use of the cover plates.)

Both ventilators are on freeboard deck in forward well, one aft of

No.2 hatch inside line of openings, and one forward of No.2 hatch port side.

Compensation doublers of adequate scantling have been fitted in way of ventilator outside line of opening.

On completion alterations examined and found satisfactory.

J. Nugent
Andrew Onrock

Surveyor to Lloyd's

Register of Shipping.

~~A copy of this Report has been placed on board.~~

