

"BERNY" <sup>ex</sup> ~~and~~ "BERGO"  
-----

Lengthening by 3.30 Metres.

New Dimensions:- 175' x 29' x 13.3'

Proportions:- Length = 13.18 depths.  
-----

Single copies of plans showing proposal to lengthen this ship by 6 frame spaces amidships, forwarded by the repairers through Thos. C. Rolland, Consulting Engineer.

IT IS SUBMITTED the repairers be informed that  
provided the new portion of this ship is constructed of the same scantlings as the existing part, a 600 ~~by~~ 9 m. doubling is fitted to the upper deck from the poop front to existing frame 67, two additional 15 fathom lengths of  $1\frac{1}{8}$ " cable supplied (225 fathoms in all), then on completion of a Reclassification Survey, the ship could be submitted to the Committee for reclassification as formerly, but in association with a summer draught measured from the top of keel of about 3.30 metres. No reinforcement is required on the hatch side coaming as shown on the Midship Section.

The plans should be returned to the repairers, and a copy of this letter sent to Thos. C. Rolland and the Helsingfors Surveyor.

Ltr. 1.12.55  
Ans. 28.12.55  
3 plans returned

Copy to Freeboard Dept.



© 2020  
28th December, 1955.

Lloyd's Register  
Foundation

002457-002464 0167