

G.R. 130.

40645-0P

*Imps*  
*1946*

(LLOYD'S REGISTER.)

VESSELS OF 100 TONS AND UPWARDS.



These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of Shipping.

Signal Letters (if any)..... G.D.N.N.

Official Number.	Name of Ship.	No., Date, and Port of Registry.
<u>169467</u>	EMPIRE GRENADA	11/1946 Glasgow ✓

No., Date, and Port of previous Registry (if any).

Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Motorship Single Screw	Glasgow	<u>1946</u>	Harland and Wolff, Limited Govan, Glasgow

Number of Decks ... .. One	Length from fore part of stem, to the aft side of the head of the stern post ... ..	Feet.	Tenths.
Number of Masts ... .. One and two Lower		466	0.0 ✓
Rigged ... .. Not	Main breadth to outside of plank ... ..	59	5.0 ✓
Stem ... .. Straight Raked	Depth in hold from tonnage deck to ceiling amidships ...	34	8.0 ✓
Stern ... .. Cruiser ✓	Depth in hold from upper deck to ceiling amidships, in the case of three decks and upwards ... ..	-	-
Build ... .. Clencher	Depth from top of deck at side amidships to bottom of keel...	34	9.8
Framework and description of vessel ... .. Steel Tanker	Round of beam ... ..	1	2.3
Number of Bulkheads ... .. Sixteen	Length of engine room, if any ... ..	74	9.0

Particulars of propelling Engines, etc. (if any), and Water Ballast Tanks, as supplied by Builders, Owners, or Engine Makers.


No. of sets of Engines	Description of Engines	Whether British or Foreign Made	When made	Name and address of makers	Reciprocating Engines		Rotary Engines	N.I.P. B.H.P. I.H.P. Estimated Speed of Ship	
					No. and Diameter of Cylinders in each set	Length of Stroke	No. of Cylinders in each set		
One	Reciprocating Internal Combustion Direct Acting Vertical	Engines	Engines	Harland and Wolff Limited Govan	Six	740 m.m	1500 m.m	-	255 3200 (Est:)
One	Particulars of Boilers Description... <u>S.F. Scotch</u> Number ... .. <u>Two</u> Iron or Steel... <u>Steel</u> Loaded Pressure <u>150 lbs. per sq. inch</u>	Boilers	Boilers	Harland Wolff Limited Belfast					4000 (Est:) 11½ Knots

Number of water ballast tanks, and their capacity in tons: Four - 596 tons

002522-002528-0155

*HPD*  
*17-4-46*

Yes ✓



Forward transverse bulkhead of No.2 Centre Cargo tank.

After transverse bulkhead and longitudinal bulkhead of No.1 centre tank, Port

PARTICULARS OF TONNAGE.

GROSS TONNAGE.		No. of Tons.	DEDUCTIONS ALLOWED.		No. of Tons.
Under Tonnage Deck	...	7238.40 ✓	On account of space required for propelling power		2634.07
Space or spaces between Decks	...		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from Goods or Stores of every kind not being the personal property of the Crew.		550.57
Turret or Trunk	...		These spaces are the following, viz. :— In poop and Pound Houses		
Forecastle	...	19.30	(Number of Seamen or Apprentices for whom accommodation is certified <del>60</del> or <del>67</del> including 47 Asiatic Crew.		
Bridge space <i>(Houses in)</i>	...	95.54	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows :—		
Poop <del>or Deck</del>	...	203.41	Cubic Meters.	Masters Accommn. 19.07)	
Side Houses	...			Chart Space 7.46)	
Deck Houses	...	432.58		Wireless Space 5.59)	
Chart House	...			Bosun's Stores 75.00)	248.30
Spaces for Machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894	...	242.24		Ballast Pump Spaces 24.73)	
Excess of Hatchways	...			Water Ballast Spaces 116.45)	
Gross Tonnage	...	8231.47		Total	3432.94
Deductions, as per contra	...	3432.94 ✓	23295.06		
Register Tonnage	...	4798.53	9715.22		
			13579.84		

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 833.74 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 242.24 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Forecastle, Length 49.5 feet = 92.07 tons

Bridge Length 52.0 feet = 123.45 tons

Name of Master

No. of Owners

Name, Residence, and Description of Managing Owner if there are more owners than one.

His Majesty,  
represented by the  
Minister of War Transport,  
London

Sixty four  
- 64 -

Certificate of { Service No.  
Competency No.

Mgr: Charles Molyneaux Cohan of  
the firm of H.E.Moss & Co  
26 Chapel Street,  
Liverpool, 3.

Dated 22nd March, 1946.

