

RECEIVED

29 OCT 1934

G.R. 130.
Lloyd's Register.

IN C.O.

(LLOYD'S REGISTER.)

VESSELS OF 100 TONS AND UPWARDS

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.
Signal Letters (if any) G.W.Y.M.

Official Number.	Name of Ship.	No., Date, and Port of Registry.
163,943.	Olvina.	48/1934. Hull.

No., Date, and Port of Previous Registry (if any). -----

Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steam Ship Single Screw.	South Bank-on-Tees.	1934	Smith's Dock Company Limited South Bank-on-Tees

Number of Decks	One	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post	Feet.	Tenths.
Number of Masts	Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel	160	3.5
Rigged	<u>Ketch</u>	Main breadth to outside of plank-timber	26	7.0
Stern	Cruiser	Depth in hold from tonnage deck to ceiling at midships	12	3.0
Build	Clincher	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards	--	--
Galleries	None	Depth from top of beam amidships to top of keel	15	6.6
Head	Straight	Depth from top of deck at side amidships to bottom of keel	15	6.2
Framework and description of vessel	Steel Fishing	Round of beam	--	6.7
Number of Bulkheads	Five	Length of engine room, if any	35	0.0
Number of water ballast tanks, and their capacity in tons	Six-52½ tons.			

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel } 702 Tons. Ditto per inch immersion at same depth } 7.38 Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign Made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. I. H. P. Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.		
One	Vertical Surface Condensing Triple Expansion.	Engines.	Engines.	Engines.	Three			99.0
		and	and	Smith's Dock Co. Ltd., South Bank.	13½"			About 800
One	Single-ended Multitubular	Boilers.	Boilers.	Richardsons Westgarth & Co., Ltd., Hartlepool.	22½"	26"	----	About 12 Knots.
	Number One	British	1934		39"			
	Iron or Steel Steel							
	Loaded Pressure 225 lbs sq.in.							

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck	377.68	On account of space required for propelling power	196.08
Space or spaces between Decks		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	44.93
Turret or Trunk	1.79	These spaces are the following, viz. :-	
Forecastle House in		Below deck,	
Bridge space	22.14	forward and aft.	
Propeller Break		(Number of Seamen or Apprentices for whom accommodation is certified...22.....).	
Side Houses	16.44	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows :-	
Round Steel Houses		Masters Accommodation 8.95	
Chart House		and Chart Space	
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894	7.04	Wireless Space 3.28	23.65
Excess of Hatchways		Boatswain's Store 5.09	
		Water Ballast Spaces 6.33	
Gross Tonnage	425.09	Total	264.66
Deductions, as per Contra	264.66		
Register Tonnage	160.43		

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 107.58 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 17.39 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Open Forecastle L.21.0' - 20.76 tons.

Name of Master	Certificate of	Service Competency	No. No.
No. of Owners			
Name, Residence, and Description of Managing Owner if there are more owners than one.	Fritz Victor Hannes Hahn		
	Victoria Fishing Co., Limited		
	42 Victoria Avenue, Hull.		
	Bank Chambers, Parliament Street, Kingston-upon-Hull.		
	-Manager-		
	Sixty-four(64) Shares.		
Dated	28th September, 1934.		

