

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

10 SEP 1957

ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name " FAIRTRADE " Official No. 970

Port of Registry MONROVIA

This ship has been under survey at GENOA

on AUGUST 1957 and the following alterations to the conditions of

assignment of loadlines have now been effected/found:—

EFFECTED :-

Opening in ship's side for ashshoot permanently closed
by fitting a welded steel plate.

FOUND :-

1) All cargo & coaling ports permanently closed (welded to
shell plating).

2) Closing appliances of tonnage openings in bridge & poop

bulkheads consist of steel plates secured by hook bolts
spaced 15" apart in lieu of stormboards.- The hinged wood

door in after bulkhead of bridge does no longer exist and the
corresponding opening is permanently closed by welded plates.-

A small opening now exists in after bulkhead of bridge,

leading to refriger. chamber in bridge space: opening 2'-5" x

2'-4", sill 3'-7", fitted with strong hinged wood door,

secured from outside only by means of a strong toggle.

Indigo

*Noted
C.A. amended
19/9/57
EMC.*

A copy of this Report has been placed on board.