

Lloyd's Register of Shipping.

- 2 JUL 1941

Ship's Name "Silverlarch"

Official No. 144410

Memorandum of alterations reported since ship was ^{previously} surveyed for assignment of Load Lines

The tonnage opening in the shelter deck the freeing ports in the tonnage well & all overhead scuppers from the shelter tween decks have been permanently closed by steel plates. A companion strongly constructed with a solid wood hinged door 22" wide 24" height of sill & operated both sides has been fitted for access to accommodation now fitted aft. Sanitary discharges from spaces below the shelter deck have been fitted with screw down automatic non return valves controlled from the shelter deck. Lifelines have been supplied & fitted for full length of vessel on shelter deck. The work light balkheads have not been extended to the shelter deck & suitable notation should be made. The shelter tween decks have been fitted with scupper pipes to the bilge.

The closing appliances of the Saloon House are as follows: 7-15" thick panelled hinged hard wood door 26" wide 19" height of sill operated both sides.

There is an open fore-castle see sketch.

This vessel is in good condition & the efficiency of the arrangements & appliances for closing hatchways & other openings in the shelter deck are satisfactory.

Clive Bell.

30/6/41

W. Hartlepool

Lucas base

See L4-4-0

Noted
 3/7/41



© 2020

Lloyd's Register
Foundation