

Lloyd's Register of Shipping.

Ship's Name M. V. "SILVERTEAK."Official No. 161486

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines

~~in~~ The vessel at this time has been converted from the War Emergency measure "closed" shelter deck type to the original open shelter deck type.

(1) The tonnage opening in the shelter deck has been restored and is closed by hatchboards and tarpaulins. The openings in the tonnage well bulkheads are now closed by shifting boards in rivetted channels for the full height.

* The five inch screw down nonreturn valves in the tonnage well have been restored.

(2) All scuppers from the shelter tween decks which were lead to the hold bilges have been blanked off.

(3) Two scuppers port and two scuppers starboard are lead to the engine room bilges and are fitted with lever weighted cocks on the open end.

(4) All shelter tween deck bulkheads pierced to allow free passage of water fore and aft.

(5) All shelter tween deck bulkheads have been opened. Appertures port and starboard 4 ft x 3 ft. are fitted with shifting boards in riveted channels for the full height.

(6) All hatchways on the second deck, are fitted with coamings, covers, supports, bearing surfaces, tarpaulins, cleats and battening arrangements and are in accordance with the Rules.

(7) There are no openings in the machinery casings in the shelter tween decks.

The following freeboards have been assigned and checked on the ships sides:-

Freeboard amidships from top of Deck Line (Steel Deck.)

Tropical Fresh Water	2 ft. 10 $\frac{1}{2}$ ins.	13 $\frac{1}{2}$ ins. above.
----------------------	-----------------------------	------------------------------

Fresh Water	3 " 5 $\frac{1}{2}$ "	7 " "
-------------	-----------------------	-------

Tropical	3 " 5 $\frac{1}{2}$ "	6 $\frac{1}{2}$ " "
----------	-----------------------	---------------------

Summer	4 " 0 $\frac{1}{2}$ "	
--------	-----------------------	--

Winter	4 " 7 "	6 $\frac{1}{2}$ " below
--------	---------	-------------------------

Winter North Atlantic	/	/
-----------------------	---	---

This certificate remains in force until the 12th. March 1948 or the arrival of New Certificates from the U.K.

* The extended spindles from the tonnage well screw down nonreturn valves remain to be fitted.

CALCUTTA

19th. May 1946.

SURVEYOR TO LLOYD'S REGISTER

CALCUTTA.

Rs. 100/-

25th
1946
28 JUN 1946