

COPY.

Lloyd's Register of Shipping



Port Vancouver, B. C.

11th December, 1943.

No. 617

This is to Certify that

R. KNOX

the undersigned Surveyor to this Society did at the request of Messrs. Vancouver Iron Works, Limited, Vancouver, B.C., attend at their plant for the purpose of examining during construction one steam drum and two water drums, intended for a Yarrow Water-tube Boiler to the order of Messrs. Foster Wheeler, Limited, St. Catherines, Ontario, and intended for a Frigate building for the Royal Canadian Navy.

The material has been tested by the Surveyors to Lloyd's Register; the scantlings are in accordance with the Society's Rules for a working pressure of 225 lbs. per square inch, and the workmanship is good. The welding has been carried out and tested in accordance with the Society's Rules for Class 1 Fusion Welded Pressure Vessels.

The three drums were tested by hydraulic pressure to 388 lbs. per square inch, showed no signs of weakness and were found tight and sound in every respect at that pressure.

These drums are being despatched to Canadian International Paper Co. Limited, Three Rivers, Quebec, for tubing and assembly and should be subjected to a further hydraulic test to the Rule pressure on completion of the installation.

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:

"While the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."

The drums are stamped for identification as follows:-

No. 617
LLOYD'S TEST
388 lbs.
W.P. 225 lbs.
22 - 11 - 43.
R.K.

R. K. W. G.

SURVEYOR TO LLOYD'S REGISTER.



© 2020

Lloyd's Register
Foundation

002592-002601-0163 2