

COPY

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER



Port

MONTREAL

4th June, 1958.

This is to Certify that

Wm. HEATLIE

the undersigned Surveyor to this Society did at the request of the Owners Representative attend on board the S.S. "COLLIER", 1858 tons gross of Montreal while lying in the dry dock at Kingston on February 5th, 1958 and subsequently for the purpose of ascertaining the nature and extent of the damage stated to have been caused by grounding at Rapide de Plat on November 18th, 1956 whilst on voyage from Oswego to Cornwall in loaded condition.

For further particulars please see vessel's Log Books.

Upon examination the undersigned:-

FOUND

BOTTOM SHELL PLATING PORT SIDE FORWARD

"A" strake, plate No. 1; "B" strake, plates Nos. 2 and 3 and "C" strake, plate No. 2 indented and set up.

STARBOARD SIDE FORWARD

"C" strake, plate No. 3 and "D" strake plates Nos. 3, 4 and 5 indented and set up.

8 bottom frames buckled

9 reverse frames buckled.

23 floors buckled.

6 bilge brackets buckled.

5 intercostals buckled.

RECOMMENDED

All to be renewed.

All to be renewed.

To be cropped and part renewed.

To be renewed.

To be cropped and part renewed.

To be renewed.

To be renewed.

All removals to be made as necessary to carry out the above recommended repairs and afterwards replaced with part new materials as required.

On completion all repaired and disturbed work to be tested and proven tight and afterwards coated.

These recommendations have been made with a view to the vessel being placed, as far as practicable, in the same condition as before the alleged casualty occurred and have now been carried out to my satisfaction.

Wm. Heatlie
SURVEYOR TO LLOYD'S REGISTER
(Wm. HEATLIE)

is issued upon the terms of the Rules and Regulations of the Society, which provide that:-

The Committees of the Society use their best endeavours to ensure that the functions of the Society are properly carried out. It is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Members or any Member thereof, or the Surveyors, or other Officers or Agents of the Society.